

Honolulu High-Capacity Transit Corridor Project Fixed Guideway Alternatives Summary Cost Comparison of Alternative Analysis <small>New Start Project (East Kapolei to Ala Moana Center)</small> <div>date:05/04/07</div>				East Kapolei to Ala Moana Center	
				Preliminary - Not Final (2006\$ with Contingency)	Preliminary - Not Final (2006\$ with Contingency)
				Sections & Alignments	Sections & Alignments
				Section 1	Section 2
Description				Saratoga Ave/North-South Rd from UHWO-Makai Station Alt 5 5 At-grade/elevated	Fort Weaver Rd to Aloha Stadium 1 At-grade/elevated
10.00	GUIDEWAY & TRACK ELEMENTS				
	10.01	Guideway: At-grade Exclusive Right-of-way		\$2,068,368	
	10.04	Guideway: Aerial structure		\$98,768,007	\$265,825,986
	10.06	Guideway: Underground cut & cover		\$0	\$19,347,000
	10.08	Guideway: Retained cut or fill		\$7,420,200	\$9,893,600
	10.09	Track: Direct fixation		\$8,750,025	\$22,999,950
	10.11	Track: Ballasted		\$3,165,612	\$753,000
	10.12	Track: Special (switches, turnouts)		\$2,969,460	\$4,633,684
	SUBTOTAL GUIDEWAY & TRACK			\$123,141,672	\$323,453,220
20.00	STATIONS, STOPS, TERMINALS, INTERMODAL				
	20.01	At-grade station, stop, shelter, mall, terminal, platform		\$3,195,536	\$3,195,536
	20.02	Aerial station, stop, shelter, mall, terminal, platform		\$11,881,180	\$23,762,360
	20.07	Elevators, escalators		\$6,504,240	\$13,008,480
	SUBTOTAL COST STATIONS, STOPS, TERMINALS, INTERMODAL			\$21,580,956	\$39,966,376
30.00	YARDS, SHOPS, ADMIN/SUPPORT FACILITIES				
	30.01	Administration Building: Office, sales, storage, revenue counting		\$0	\$0
	30.03	Heavy Maintenance Facility		\$0	\$0
	30.04	Storage Building & Yard		"IN 30.03"	"IN 30.03"
	SUBTOTAL COST YARDS, SHOPS, ADMIN/SUPPORT FACILITIES			\$0	\$0
40.00	SITEWORK & SPECIAL CONDITIONS				
	40.01	Demolition, Clearing, Earthwork ¹		\$2,474,018	\$7,463,018
	40.02	Site Utilities, Utility Relocation		\$12,515,940	\$17,431,423
	40.03	Haz. mat'l, contam'd soil removal/mitigation, ground water treatments		\$237,355	\$3,250,635
	40.04	Environmental mitigation, e.g. wetlands, historic/archeologic, parks		\$750,000	\$2,500,000
	40.06	Site Development: Roads, walks, plazas, parking lots, landscape work		\$33,172,332	\$97,827,729
	SUBTOTAL COST SITEWORK & SPECIAL CONDITIONS			\$49,149,645	\$128,472,805
50.00	SYSTEMS				
	50.01	Train control and signals		\$6,468,246	\$8,466,612
	50.02	Traffic signals and crossing protection		\$0	\$8,073,364
	50.03	Traction power supply: substations		\$6,561,844	\$11,483,227
	50.04	Traction power distribution: catenary and third rail		\$4,957,065	\$8,535,150
	50.05	Communications		\$5,761,431	\$10,636,626
	50.06	Fare collection system and equipment		\$899,136	\$1,498,560
	50.07	Central Control		\$0	\$0
	SUBTOTAL COST SYSTEMS			\$24,647,722	\$48,693,539
		SUBTOTAL CONSTRUCTION COSTS		\$218,519,995	\$540,585,940
		CONTINGENCY (WEIGHTED AVERAGE)		\$56,227,730	\$140,145,693
	SUBTOTAL CONSTRUCTION COSTS WITH CONTINGENCY			\$274,747,725	\$680,731,633
		FEE/RISK		in items above	in items above
		ADJUSTMENT FOR CASUAL OVERTIME	(2.5% OF DIRECT LABOR)	\$1,803,032	\$4,467,301
		SUBTOTAL CONSTRUCTION COSTS		\$276,550,757	\$685,198,934
		HAWAII STATE EXCISE	4.712%	\$13,031,072	\$32,286,574
		TOTAL CONSTRUCTION COSTS (2006\$)		\$289,581,829	\$717,485,508

Honolulu High-Capacity Transit Corridor Project Fixed Guideway Alternatives Summary Cost Comparison of Alternative Analysis New Start Project (East Kapolei to Ala Moana Center)				East Kapolei to Ala Moana Center				
				Preliminary - Not Final (2006\$ with Contingency)		Preliminary - Not Final (2006\$ with Contingency)		
				Sections & Alignments		Sections & Alignments		
				Section 1		Section 2		
Description				Saratoga Ave/North-South Rd from UHWO-Makai Station		Fort Weaver Rd to Aloha Stadium		
				ROW, LAND, EXISTING IMPROVEMENTS				
				60.01	Purchase or lease of real property		\$0	\$3,320,000
				60.02	Relocation of existing households and businesses		\$0	\$400,000
					SUBTOTAL COST ROW, LAND, EXISTING IMPROVEMENTS		\$0	\$3,720,000
					CONTINGENCY & ENGINEERING (40%+10%)	50%	\$0	\$1,860,000
				TOTAL ROW COSTS		\$0	\$5,580,000	
70.00				VEHICLES				
				70.01	Light Rail		IN SECTION 6	IN SECTION 6
				70.06	Non-revenue vehicles		IN SECTION 6	IN SECTION 6
				70.07	Spare parts (10% of LRV's)		IN SECTION 6	IN SECTION 6
					SUBTOTAL VEHICLE COST		\$0	\$0
					CONTINGENCY & ENGINEERING STAFF(10%+14%)	24%	\$0	\$0
				TOTAL VEHICLE COSTS		\$0	\$0	
80.00				SOFT COSTS				
				80.01	Preliminary Engineering	3.0%	\$8,687,455	\$21,524,565
				80.02	Final Design	4.5%	\$13,031,182	\$32,286,848
				80.03	Project Management for Design and Construction	5.5%	\$15,927,001	\$39,461,703
				80.04	Construction Administration & Management	10.0%	\$28,958,183	\$71,748,551
				80.05	Insurance-Professional liability	1.50%	\$4,343,727	\$10,762,283
				80.06	Legal, Permits, Review Fees by other agencies, cities, etc	1.50%	\$4,343,727	\$10,762,283
				80.07	Survey, Testing, Investigation, Inspection	0.50%	\$1,447,909	\$3,587,428
				80.08	Agency: Force Account Work (2% ^{3,4})	3.5%	\$10,135,364	\$25,111,993
				SUBTOTAL SOFT COSTS		30%	\$86,874,549	\$215,245,652
90.00				CONTINGENCY (Project Reserve) (10 thru 80)		6.0%	\$22,587,383	\$56,298,670
100.00				FINANCE CHARGES			\$0	\$0
110.00				Total Construction (10+20+30+40+50) (2006\$)			\$289,581,829	\$717,485,508
				OTHER PROJECT COST (60+70+80+90+100) (2006\$)			\$109,461,931	\$277,124,322
				TOTAL PROJECT COST (10+20+30+40+50+60+70+80+90+100) (2006\$)			\$399,043,760	\$994,609,829
				Route foot length		19,269'	35,574'	
				Construction Cost per Route Foot (2006\$)		\$15,000	\$20,200	
				Construction Cost per Route Mile (2006\$)		\$79,200,000	\$106,656,000	

<div> <div>Honolulu High-Capacity Transit Corridor Project</div> <div>Fixed Guideway Alternatives</div> <div>Summary Cost Comparison of Alternative Analysis</div> <div>New Start Project (East Kapolei to Ala Moana Center)</div> <div> <div>date:</div> <div>05/04/07</div> </div> </div>				East Kapolei to Ala Moana Center	
				Preliminary - Not Final (2006\$ with Contingency)	Preliminary - Not Final (2006\$ with Contingency)
				Sections & Alignments	Sections & Alignments
				Section 3	Section 4
Description				Salt Lake Blvd/Dillingham Blvd	Dillingham Blvd
				section 3 alt 2	
				15	18
				Elevated	Elevated
10.00	GUIDEWAY & TRACK ELEMENTS				
	10.01	Guideway: At-grade Exclusive Right-of-way			
	10.04	Guideway: Aerial structure		\$203,521,800	\$71,662,950
	10.06	Guideway: Underground cut & cover		\$0	\$0
	10.08	Guideway: Retained cut or fill		\$0	\$0
	10.09	Track: Direct fixation		\$16,856,100	\$5,935,275
	10.11	Track: Ballasted		\$0	\$0
	10.12	Track: Special (switches, turnouts)		\$1,914,822	\$2,872,233
	SUBTOTAL GUIDEWAY & TRACK			\$222,292,722	\$80,470,458
20.00	STATIONS, STOPS, TERMINALS, INTERMODAL				
	20.01	At-grade station, stop, shelter, mall, terminal, platform		\$0	\$0
	20.02	Aerial station, stop, shelter, mall, terminal, platform		\$11,737,180	\$17,821,770
	20.07	Elevators, escalators		\$6,504,240	\$9,756,360
	SUBTOTAL COST STATIONS, STOPS, TERMINALS, INTERMODAL			\$18,241,420	\$27,578,130
30.00	YARDS, SHOPS, ADMIN/SUPPORT FACILITIES				
	30.01	Administration Building: Office, sales, storage, revenue counting		\$0	\$0
	30.03	Heavy Maintenance Facility		\$0	\$0
	30.04	Storage Building & Yard		"IN 30.03"	"IN 30.03"
	SUBTOTAL COST YARDS, SHOPS, ADMIN/SUPPORT FACILITIES			\$0	\$0
40.00	SITEWORK & SPECIAL CONDITIONS				
	40.01	Demolition, Clearing, Earthwork ¹		\$5,169,204	\$1,820,151
	40.02	Site Utilities, Utility Relocation		\$18,860,936	\$72,140,805
	40.03	Haz. mat'l, contam'd soil removal/mitigation, ground water treatments		\$154,290	\$2,313,240
	40.04	Environmental mitigation, e.g. wetlands, historic/archeologic, parks		\$2,500,000	\$2,500,000
	40.06	Site Development: Roads, walks, plazas, parking lots, landscape work		\$16,974,210	\$5,931,451
	SUBTOTAL COST SITEWORK & SPECIAL CONDITIONS			\$43,658,640	\$84,705,647
50.00	SYSTEMS				
	50.01	Train control and signals		\$5,943,336	\$2,092,734
	50.02	Traffic signals and crossing protection		\$5,151,512	\$2,835,328
	50.03	Traction power supply: substations		\$8,202,305	\$3,280,922
	50.04	Traction power distribution: catenary and third rail		\$5,618,700	\$1,978,425
	50.05	Communications		\$7,466,628	\$2,629,107
	50.06	Fare collection system and equipment		\$599,424	\$899,136
	50.07	Central Control		\$0	\$0
	SUBTOTAL COST SYSTEMS			\$32,981,905	\$13,715,652
		SUBTOTAL CONSTRUCTION COSTS		\$317,174,687	\$206,469,887
		CONTINGENCY (WEIGHTED AVERAGE)		\$81,962,115	\$59,494,891
	SUBTOTAL CONSTRUCTION COSTS WITH CONTINGENCY			\$399,136,801	\$265,964,779
		FEE/RISK		in items above	in items above
		ADJUSTMENT FOR CASUAL OVERTIME	(2.5% OF DIRECT LABOR)	\$2,619,335	\$1,745,394
		SUBTOTAL CONSTRUCTION COSTS		\$401,756,137	\$267,710,173
		HAWAII STATE EXCISE	4.712%	\$18,930,749	\$12,614,503
		TOTAL CONSTRUCTION COSTS (2006\$)		\$420,686,886	\$280,324,676

Honolulu High-Capacity Transit Corridor Project Fixed Guideway Alternatives Summary Cost Comparison of Alternative Analysis New Start Project (East Kapolei to Ala Moana Center)				East Kapolei to Ala Moana Center			
				Preliminary - Not Final (2006\$ with Contingency)		Preliminary - Not Final (2006\$ with Contingency)	
				Sections & Alignments		Sections & Alignments	
				Section 3		Section 4	
date: 05/04/07							
Description				Salt Lake Blvd/Dillingham Blvd			
				Dillingham Blvd			
60.00	ROW, LAND, EXISTING IMPROVEMENTS						
	60.01	Purchase or lease of real property		\$4,720,000	\$6,540,000		
	60.02	Relocation of existing households and businesses		\$0	\$0		
	SUBTOTAL COST ROW, LAND, EXISTING IMPROVEMENTS			\$4,720,000	\$6,540,000		
	CONTINGENCY & ENGINEERING (40%+10%)		50%	\$2,360,000	\$3,270,000		
	TOTAL ROW COSTS			\$7,080,000	\$9,810,000		
	70.00	VEHICLES					
70.01		Light Rail		IN SECTION 6	IN SECTION 6		
70.06		Non-revenue vehicles		IN SECTION 6	IN SECTION 6		
70.07		Spare parts (10% of LRV's)		IN SECTION 6	IN SECTION 6		
SUBTOTAL VEHICLE COST			\$0	\$0			
CONTINGENCY & ENGINEERING STAFF(10%+14%)		24%	\$0	\$0			
TOTAL VEHICLE COSTS			\$0	\$0			
80.00	SOFT COSTS						
	80.01	Preliminary Engineering	3.0%	\$12,620,607	\$8,409,740		
	80.02	Final Design	4.5%	\$18,930,910	\$12,614,610		
	80.03	Project Management for Design and Construction	5.5%	\$23,137,779	\$15,417,857		
	80.04	Construction Administration & Management	10.0%	\$42,068,689	\$28,032,468		
	80.05	Insurance-Professional liability	1.50%	\$6,310,303	\$4,204,870		
	80.06	Legal, Permits, Review Fees by other agencies, cities, etc	1.50%	\$6,310,303	\$4,204,870		
	80.07	Survey, Testing, Investigation, Inspection	0.50%	\$2,103,434	\$1,401,623		
	80.08	Agency: Force Account Work (2% ^{3,4})	3.5%	\$14,724,041	\$9,811,364		
	SUBTOTAL SOFT COSTS		30%	\$126,206,066	\$84,097,403		
	90.00	CONTINGENCY (Project Reserve) (10 thru 80)		6.0%	\$33,238,377	\$22,453,925	
100.00	FINANCE CHARGES			\$0	\$0		
110.00	Total Construction (10+20+30+40+50) (2006\$)			\$420,686,886	\$280,324,676		
	OTHER PROJECT COST (60+70+80+90+100) (2006\$)			\$166,524,443	\$116,361,328		
	TOTAL PROJECT COST (10+20+30+40+50+60+70+80+90+100) (2006\$)			\$587,211,328	\$396,686,004		
Route foot length				24,972'	8,793'		
Construction Cost per Route Foot (2006\$)				\$16,800	\$31,900		
Construction Cost per Route Mile (2006\$)				\$88,704,000	\$168,432,000		

Honolulu High-Capacity Transit Corridor Project Fixed Guideway Alternatives Summary Cost Comparison of Alternative Analysis <small>New Start Project (East Kapolei to Ala Moana Center)</small> <div>date:05/04/07</div>				East Kapolei to Ala Moana Center	
				Preliminary - Not Final (2006\$ with Contingency)	Preliminary - Not Final (2006\$ with Contingency)
				Sections & Alignments	Sections & Alignments
				Section 5	Section 6
Description				Dillingham/Nimitz Hwy/Halekauwila St/Kapiolani Blvd to Ala Moana Sta	Systemwide
					Alt 11
				25	26
				Elevated	Elevated
10.00	GUIDEWAY & TRACK ELEMENTS				
	10.01	Guideway: At-grade Exclusive Right-of-way			
	10.04	Guideway: Aerial structure		\$118,816,510	\$0
	10.06	Guideway: Underground cut & cover		\$0	\$0
	10.08	Guideway: Retained cut or fill		\$0	\$0
	10.09	Track: Direct fixation		\$9,803,700	\$0
	10.11	Track: Ballasted		\$0	\$0
	10.12	Track: Special (switches, turnouts)		\$5,793,564	\$0
	SUBTOTAL GUIDEWAY & TRACK			\$134,413,774	\$0
20.00	STATIONS, STOPS, TERMINALS, INTERMODAL				
	20.01	At-grade station, stop, shelter, mall, terminal, platform		\$0	\$0
	20.02	Aerial station, stop, shelter, mall, terminal, platform		\$36,696,688	\$0
	20.07	Elevators, escalators		\$17,945,931	\$0
	SUBTOTAL COST STATIONS, STOPS, TERMINALS, INTERMODAL			\$54,642,619	\$0
30.00	YARDS, SHOPS, ADMIN/SUPPORT FACILITIES				
	30.01	Administration Building: Office, sales, storage, revenue counting		\$0	\$14,758,888
	30.03	Heavy Maintenance Facility		\$0	\$66,456,265
	30.04	Storage Building & Yard		"IN 30.03"	"IN 30.03"
	SUBTOTAL COST YARDS, SHOPS, ADMIN/SUPPORT FACILITIES			\$0	\$81,215,153
40.00	SITEWORK & SPECIAL CONDITIONS				
	40.01	Demolition, Clearing, Earthwork ¹		\$3,006,468	\$0
	40.02	Site Utilities, Utility Relocation		\$126,787,082	\$0
	40.03	Haz. mat'l, contam'd soil removal/mitigation, ground water treatments		\$0	\$0
	40.04	Environmental mitigation, e.g. wetlands, historic/archeologic, parks		\$750,000	\$0
	40.06	Site Development: Roads, walks, plazas, parking lots, landscape work		\$5,406,413	\$0
	SUBTOTAL COST SITEWORK & SPECIAL CONDITIONS			\$135,949,963	\$0
50.00	SYSTEMS				
	50.01	Train control and signals		\$3,456,712	\$0
	50.02	Traffic signals and crossing protection		\$6,336,226	\$0
	50.03	Traction power supply: substations		\$4,921,383	\$0
	50.04	Traction power distribution: catenary and third rail		\$3,267,900	\$0
	50.05	Communications		\$4,342,676	\$0
	50.06	Fare collection system and equipment		\$1,798,272	\$0
	50.07	Central Control		\$0	\$8,529,933
	SUBTOTAL COST SYSTEMS			\$24,123,169	\$8,529,933
		SUBTOTAL CONSTRUCTION COSTS		\$349,129,524	\$89,745,086
		CONTINGENCY (WEIGHTED AVERAGE)		\$100,336,736	\$22,436,272
	SUBTOTAL CONSTRUCTION COSTS WITH CONTINGENCY			\$449,466,260	\$112,181,358
		FEE/RISK		in items above	in items above
		ADJUSTMENT FOR CASUAL OVERTIME	(2.5% OF DIRECT LABOR)	\$2,949,622	\$736,190
		SUBTOTAL CONSTRUCTION COSTS		\$452,415,883	\$112,917,548
		HAWAII STATE EXCISE	4.712%	\$21,317,836	\$5,320,675
		TOTAL CONSTRUCTION COSTS (2006\$)		\$473,733,719	\$118,238,223

Honolulu High-Capacity Transit Corridor Project Fixed Guideway Alternatives Summary Cost Comparison of Alternative Analysis New Start Project (East Kapolei to Ala Moana Center)				East Kapolei to Ala Moana Center			
				Preliminary - Not Final (2006\$ with Contingency)		Preliminary - Not Final (2006\$ with Contingency)	
				Sections & Alignments		Sections & Alignments	
				Section 5		Section 6	
Description				Dillingham/Nimitz Hwy/Halekauwila St/Kapiolani Blvd to Ala Moana Sta	Systemwide		
60.00							
	ROW, LAND, EXISTING IMPROVEMENTS						
	60.01	Purchase or lease of real property		\$31,800,000	\$0		
	60.02	Relocation of existing households and businesses		\$1,300,000	\$0		
		SUBTOTAL COST ROW, LAND, EXISTING IMPROVEMENTS		\$33,100,000	\$0		
		CONTINGENCY & ENGINEERING (40%+10%)		50%	\$16,550,000	\$0	
	TOTAL ROW COSTS			\$49,650,000	\$0		
70.00	VEHICLES						
	70.01	Light Rail		IN SECTION 6	\$162,804,312		
	70.06	Non-revenue vehicles		IN SECTION 6	\$4,203,149		
	70.07	Spare parts (10% of LRV's)		IN SECTION 6	\$16,280,418		
		SUBTOTAL VEHICLE COST		\$0	\$183,287,879		
		CONTINGENCY & ENGINEERING STAFF(10%+14%)		24%	\$0	\$43,989,091	
	TOTAL VEHICLE COSTS			\$0	\$227,276,970		
80.00	SOFT COSTS						
	80.01	Preliminary Engineering	3.0%	\$14,212,012	\$3,547,147		
	80.02	Final Design	4.5%	\$21,318,017	\$5,320,720		
	80.03	Project Management for Design and Construction	5.5%	\$26,055,355	\$6,503,102		
	80.04	Construction Administration & Management	10.0%	\$47,373,372	\$11,823,822		
	80.05	Insurance-Professional liability	1.50%	\$7,106,006	\$1,773,573		
	80.06	Legal, Permits, Review Fees by other agencies, cities, etc	1.50%	\$7,106,006	\$1,773,573		
	80.07	Survey, Testing, Investigation, Inspection	0.50%	\$2,368,669	\$591,191		
	80.08	Agency: Force Account Work (2% ^{3,4})	3.5%	\$16,580,680	\$4,138,338		
	SUBTOTAL SOFT COSTS		30%	\$142,120,116	\$35,471,467		
	90.00	CONTINGENCY (Project Reserve) (10 thru 80)		6.0%	\$39,930,230	\$22,859,200	
100.00	FINANCE CHARGES			\$0	\$0		
110.00	Total Construction (10+20+30+40+50) (2006\$)			\$473,733,719	\$118,238,223		
	OTHER PROJECT COST (60+70+80+90+100) (2006\$)			\$231,700,346	\$285,607,636		
	TOTAL PROJECT COST (10+20+30+40+50+60+70+80+90+100) (2006\$)			\$705,434,065	\$403,845,859		
Route foot length			14,524'				
Construction Cost per Route Foot (2006\$)			\$32,600				
Construction Cost per Route Mile (2006\$)			\$172,128,000				

Honolulu High-Capacity Transit Corridor Project								
Fixed Guideway Alternatives								
Summary Cost Comparison of Alternative Analysis								
Pricing Sheet								
Guideway & Trackwork								
New Start Project (East Kapolei to Ala Moana Center)								
					Saratoga Ave/North-South Rd from UHWO-Makai Station		Fort Weaver Rd to Aloha Stadium	
COST					Section 1 Alt 5a		Section 2 Alt 1	
DESCRIPTION	ID	QTY	UNIT					
1	2	3	4	5	64	65	22	23
10.00 GUIDEWAY & TRACK ELEMENTS (route miles)								
Guideway: At-grade Exclusive								
csc10.01-1	Single At-Grade Ballasted Trackbed - Open	1	RF	\$260	-	\$0	-	\$0
csc10.01-2	Double At-Grade Ballasted Trackbed - Open	1	RF	\$328	6,306	\$2,068,368	-	\$0
csc10.01-5	Single At-Grade Guideway for Paved Track	1	RF	**NOT USED	-		-	
csc10.01-6	Double At-Grade Guideway for Paved Track	1	RF	**NOT USED	-		-	
10.01	Guideway: At-grade Exclusive		RF			\$2,068,368		\$0
10.02	Guideway: At-grade semi-exclusive (allows cross-traffic) NOT USED*****					**NOT USED**		**NOT USED**
Guideway: At-grade in mixed traffic								
csc10.01-4	Double At-Grade Guideway for Paved Track	1	RF	\$365	0	\$0	-	\$0
10.03	Guideway: At-grade in mixed traffic		RF			\$0		\$0
Guideway: Aerial structure								
csc10.04-1	Segmental Aerial Structure (T/R +25 Ft.) Column (6 ft Dia)	1	RF	\$7,989	12,363	\$98,768,007	33,274	\$265,825,986
csc10.04-2a	Standard Aerial Dual Structure (T/R +30 Ft.) CIP	1	RF	\$5,993	-	\$0	-	\$0
csc10.04-2	Segmental Aerial Structure (T/R +30 Ft.) Column (6 ft Dia)	1	RF	\$8,086	-	\$0	-	\$0
csc10.04-3	Segmental Aerial Structure (T/R +40 Ft.) Column (6 ft Dia)	1	RF	\$8,150	-	\$0	-	\$0
csc10.04-4	Segmental Aerial Structure (T/R +50 Ft.) Column (8 ft Dia)	1	RF	\$8,452	-	\$0	-	\$0
csc10.04-5	Segmental Aerial Structure (T/R +60 Ft.) Column (8 ft dia)	1	RF	\$8,709	-	\$0	-	\$0
csc10.04-6	Standard Aerial Dual Structure (T/R +30 Ft.) Cast - in Place	1	RF	\$5,793	-	\$0	-	\$0
csc10.04-6X	FACTOR FOR DOWNTOWN AERIAL STRUCTURE	1	%	30%		\$0		\$0
10.04	Guideway: Aerial structure		RF		12,363	\$98,768,007	\$33,274	\$265,825,986
10.05	Guideway: Built-up fill not used*****							
Guideway: Underground cut & cover								
csc10.06-1	Cut & Cover, Tunnel (TBM) , Portal, U Wall (Hotel St / Kawaiano / K	1	RF	\$34,090	-	\$0	-	\$0
csc10.06-2	U-Wall Retained Cut Dual Track Portal (Avg. Depth 25 ft)	1	RF	\$12,898	-	\$0	1,500	\$19,347,000
10.06	Guideway: Underground cut & cover		RF			\$0		\$19,347,000
Guideway: Underground tunnel								
csc10.07-1	Tunnel, Portal and U-Wall (Hotel Waimanu / Kapiolani Blvd)	1	RF	\$31,308	-	\$0	-	\$0
csc10.07-2	Tunnel, Portal and U-Wall (North King \ Bertania St \ S King St)	1	RF	\$25,129	-	\$0	-	\$0
csc10.07-3	Tunnel, Portal and U-Wall (Dillingham \ Bertania St \ S King St)	1	RF	\$25,129	-	\$0	-	\$0
csc10.07-4	Tunnel, Portal and U-Wall (King St Option 1 sta 1315+55 to 1408+91	1	RF	\$26,088	-	\$0	-	\$0
csc10.07-5	Tunnel, Portal and U-Wall (King St Option 2 sta 1348+50 to 1408+91	1	RF	\$27,920	-	\$0	-	\$0
10.07	Guideway: Underground tunnel		-			\$0		\$0
Guideway: Retained cut or fill								
csc10.08-1	Abutment Double At-Grade (Avg. D. T/R +10 Ft.) 100 ft length	1	RF	\$12,367	600	\$7,420,200	800	\$9,893,600
csc10.08-2	Abutment Single At-Grade (Avg. D. T/R +10 Ft.)	1	RF	\$6,162	-	\$0	-	\$0
10.08	Guideway: Retained cut or fill		RF			\$7,420,200		\$9,893,600
Track: Direct fixation								
csc10.09-1	Direct Fixation Track - Single	1	RF	\$435	-	\$0	-	\$0
csc10.09-2	Direct Fixation Dual Track	1	RF	\$675	12,963	\$8,750,025	34,074	\$22,999,950
10.09	Track: Direct fixation		RF			\$8,750,025		\$22,999,950
Track: Embedded/Paved								
csc10.10-1	Paved Track (In Street) - Single	1	RF	\$667	-	\$0	-	\$0
csc10.10-2	Paved Track (In Street) - DUAL	1	RF	\$1,250	-	\$0	-	\$0
10.10	Track: Embedded/Paved		RF			\$0		\$0
Track: Ballasted								
csc10.11-1	Ballasted Track (Open) - Single	1	RF	\$247	-	\$0	-	\$0
csc10.11-2	Ballasted Track (Open) - Double	1	RF	\$502	6,306	\$3,165,612	1,500	\$753,000
10.11	Track: Ballasted		RF			\$3,165,612		\$753,000
Track: Special (switches, turnouts)								
csc10.12-1	Double Crossover DF (No. 10)	1	EA	\$957,411	2	\$1,914,822	4	\$3,829,644
csc10.12-2	Double Crossover Ballasted (No. 10)	1	EA	\$804,040	1	\$804,040	1	\$804,040
csc10.12-3	No. 6 Turnout - DF	1	EA	\$282,314		\$0		\$0
csc10.12-4	No. 5 Turnout - DF	1	EA	\$135,258		\$0		\$0
csc10.12-5	Permanent Terminal, Direct Fixation	1	EA	\$24,549	2	\$49,098		\$0
csc10.12-6	Grade Crossing Panels (Dual Track)	1	EA	\$650	310	\$201,500	0	\$0
10.12	Track: Special (switches, turnouts)		LS			\$2,969,460		\$4,633,684
Track: Vibration and noise dampening								
csc10.13-1	Track Vibration and Noise Dampening	1	RF	\$1,074	\$	\$0		\$0
10.13	Vibration and noise dampening		RF			\$0		\$0
Total Guideways							\$123,141,672	\$323,453,220

Honolulu High-Capacity Transit Corridor Project Fixed Guideway Alternatives Summary Cost Comparison of Alternative Analysis Pricing Sheet Guideway & Trackwork New Start Project (East Kapolei to Ala Moana Center)								
					Salt Lake Blvd/Dillingham Blvd		Dillingham Blvd	
COST					Section 3 Alt 2		Section 4 Alt 3	
DESCRIPTION	ID	QTY	UNIT					
1	2	3	4	5	26	27	40	41
10.00 GUIDEWAY & TRACK ELEMENTS (route miles)								
Guideway: At-grade Exclusive								
csc10.01-1	Single At-Grade Ballasted Trackbed - Open	1	RF	\$260	-	\$0	-	\$0
csc10.01-2	Double At-Grade Ballasted Trackbed - Open	1	RF	\$328	-	\$0	-	\$0
csc10.01-5	Single At-Grade Guideway for Paved Track	1	RF	**NOT USED	-		-	
csc10.01-6	Double At-Grade Guideway for Paved Track	1	RF	**NOT USED	-		-	
10.01	Guideway: At-grade Exclusive		RF			\$0		\$0
10.02	Guideway: At-grade semi-exclusive (allows cross-traffic) NOT USED*****				**NOT USED**		**NOT USED**	
Guideway: At-grade in mixed traffic								
csc10.01-4	Double At-Grade Guideway for Paved Track	1	RF	\$365	-	\$0	0	\$0
10.03	Guideway: At-grade in mixed traffic		RF			\$0		\$0
Guideway: Aerial structure								
csc10.04-1	Segmental Aerial Structure (T/R +25 Ft.) Column (6 ft Dia)	1	RF	\$7,989	-	\$0	-	\$0
csc10.04-2a	Standard Aerial Dual Structure (T/R +30 Ft.) CIP	1	RF	\$5,993	-	\$0	-	\$0
csc10.04-2	Segmental Aerial Structure (T/R +30 Ft.) Column (6 ft Dia)	1	RF	\$8,086	-	\$0	-	\$0
csc10.04-3	Segmental Aerial Structure (T/R +40 Ft.) Column (6 ft Dia)	1	RF	\$8,150	24,972	\$203,521,800	8,793	\$71,662,950
csc10.04-4	Segmental Aerial Structure (T/R +50 Ft.) Column (8 ft Dia)	1	RF	\$8,452	-	\$0	-	\$0
csc10.04-5	Segmental Aerial Structure (T/R +60 Ft.) Column (8 ft dia)	1	RF	\$8,709	-	\$0	-	\$0
csc10.04-6	Standard Aerial Dual Structure (T/R +30 Ft.) Cast - in Place	1	RF	\$5,793	-	\$0	-	\$0
csc10.04-6X	FACTOR FOR DOWNTOWN AERIAL STRUCTURE	1	%	30%		\$0		\$0
10.04	Guideway: Aerial structure		RF		\$24,972	\$203,521,800	\$8,793	\$71,662,950
10.05	Guideway: Built-up fill not used*****							
Guideway: Underground cut & cover								
csc10.06-1	Cut & Cover, Tunnel (TBM) , Portal, U Wall (Hotel St / Kawaiano / K	1	RF	\$34,090	-	\$0	-	\$0
csc10.06-2	U-Wall Retained Cut Dual Track Portal (Avg. Depth 25 ft)	1	RF	\$12,898	-	\$0	-	\$0
10.06	Guideway: Underground cut & cover		RF			\$0		\$0
Guideway: Underground tunnel								
csc10.07-1	Tunnel, Portal and U-Wall (Hotel Waimanu / Kapiolani Blvd)	1	RF	\$31,308	-	\$0	-	\$0
csc10.07-2	Tunnel, Portal and U-Wall (North King \ Bertania St \ S King St)	1	RF	\$25,129	-	\$0	-	\$0
csc10.07-3	Tunnel, Portal and U-Wall (Dillingham \ Bertania St \ S King St)	1	RF	\$25,129	-	\$0	-	\$0
csc10.07-4	Tunnel, Portal and U-Wall (King St Option 1 sta 1315+55 to 1408+91	1	RF	\$26,088	-	\$0	-	\$0
csc10.07-5	Tunnel, Portal and U-Wall (King St Option 2 sta 1348+50 to 1408+91	1	RF	\$27,920	-	\$0	-	\$0
10.07	Guideway: Underground tunnel		-			\$0		\$0
Guideway: Retained cut or fill								
csc10.08-1	Abutment Double At-Grade (Avg. D. T/R +10 Ft.) 100 ft length	1	RF	\$12,367	-	\$0	-	\$0
csc10.08-2	Abutment Single At-Grade (Avg. D. T/R +10 Ft.)	1	RF	\$6,162	-	\$0	-	\$0
10.08	Guideway: Retained cut or fill		RF			\$0		\$0
Track: Direct fixation								
csc10.09-1	Direct Fixation Track - Single	1	RF	\$435	-	\$0	-	\$0
csc10.09-2	Direct Fixation Dual Track	1	RF	\$675	24,972	\$16,856,100	8,793	\$5,935,275
10.09	Track: Direct fixation		RF			\$16,856,100		\$5,935,275
Track: Embedded/Paved								
csc10.10-1	Paved Track (In Street) - Single	1	RF	\$667	-	\$0	-	\$0
csc10.10-2	Paved Track (In Street) - DUAL	1	RF	\$1,250	-	\$0	-	\$0
10.10	Track: Embedded/Paved		RF			\$0		\$0
Track: Ballasted								
csc10.11-1	Ballasted Track (Open) - Single	1	RF	\$247	-	\$0	-	\$0
csc10.11-2	Ballasted Track (Open) - Double	1	RF	\$502	-	\$0	-	\$0
10.11	Track: Ballasted		RF			\$0		\$0
Track: Special (switches, turnouts)								
csc10.12-1	Double Crossover DF (No. 10)	1	EA	\$957,411	2	\$1,914,822	3	\$2,872,233
csc10.12-2	Double Crossover Ballasted (No. 10)	1	EA	\$804,040	-	\$0	-	\$0
csc10.12-3	No. 6 Turnout - DF	1	EA	\$282,314		\$0		\$0
csc10.12-4	No. 5 Turnout - DF	1	EA	\$135,258		\$0		\$0
csc10.12-5	Permanent Terminal, Direct Fixation	1	EA	\$24,549		\$0		\$0
csc10.12-6	Grade Crossing Panels (Dual Track)	1	EA	\$650	0	\$0	0	\$0
10.12	Track: Special (switches, turnouts)		LS			\$1,914,822		\$2,872,233
Track: Vibration and noise dampening								
csc10.13-1	Track Vibration and Noise Dampening	1	RF	\$1,074	\$	\$0	\$	\$0
10.13	Vibration and noise dampening		RF			\$0		\$0
Total Guideways					\$222,292,722		\$80,470,458	

Honolulu High-Capacity Transit Corridor Project

Fixed Guideway Alternatives

Summary Cost Comparison of Alternative Analysis

Pricing Sheet

Guideway & Trackwork

New Start Project (East Kapolei to Ala Moana Center)

					Dillingham/Nimitz Hwy/Halekauwila St/Kapiolani Blvd to Ala Moana Sta	
DESCRIPTION		COST			Section 1 Alt 5a	
1	2	3	4	5	78	79
10.00 GUIDEWAY & TRACK ELEMENTS (route miles)						
Guideway: At-grade Exclusive						
csc10.01-1	Single At-Grade Ballasted Trackbed - Open	1	RF	\$260	-	\$0
csc10.01-2	Double At-Grade Ballasted Trackbed - Open	1	RF	\$328	-	\$0
csc10.01-5	Single At-Grade Guideway for Paved Track	1	RF	**NOT USED	-	
csc10.01-6	Double At-Grade Guideway for Paved Track	1	RF	**NOT USED	-	
10.01	Guideway: At-grade Exclusive		RF			\$0
10.02	Guideway: At-grade semi-exclusive (allows cross-traffic) NOT USED*****				**NOT USED**	
Guideway: At-grade in mixed traffic						
csc10.01-4	Double At-Grade Guideway for Paved Track	1	RF	\$365	-	\$0
10.03	Guideway: At-grade in mixed traffic		RF			\$0
Guideway: Aerial structure						
csc10.04-1	Segmental Aerial Structure (T/R +25 Ft.) Column (6 ft Dia)	1	RF	\$7,989	-	\$0
csc10.04-2a	Standard Aerial Dual Structure (T/R +30 Ft.) CIP	1	RF	\$5,993	12,505	\$74,942,465
csc10.04-2	Segmental Aerial Structure (T/R +30 Ft.) Column (6 ft Dia)	1	RF	\$8,086	-	\$0
csc10.04-3	Segmental Aerial Structure (T/R +40 Ft.) Column (6 ft Dia)	1	RF	\$8,150	2,019	\$16,454,850
csc10.04-4	Segmental Aerial Structure (T/R +50 Ft.) Column (8 ft Dia)	1	RF	\$8,452	-	\$0
csc10.04-5	Segmental Aerial Structure (T/R +60 Ft.) Column (8 ft dia)	1	RF	\$8,709	-	\$0
csc10.04-6	Standard Aerial Dual Structure (T/R +30 Ft.) Cast - in Place	1	RF	\$5,793	-	\$0
csc10.04-6X	FACTOR FOR DOWNTOWN AERIAL STRUCTURE	1	%	30%	1	\$27,419,195
10.04	Guideway: Aerial structure		RF		14,524	\$118,816,510
10.05	Guideway: Built-up fill not used*****					
Guideway: Underground cut & cover						
csc10.06-1	Cut & Cover, Tunnel (TBM) , Portal, U Wall (Hotel St / Kawaiano / K	1	RF	\$34,090	-	\$0
csc10.06-2	U-Wall Retained Cut Dual Track Portal (Avg. Depth 25 ft)	1	RF	\$12,898	-	\$0
10.06	Guideway: Underground cut & cover		RF			\$0
Guideway: Underground tunnel						
csc10.07-1	Tunnel, Portal and U-Wall (Hotel Waimanu / Kapiolani Blvd)	1	RF	\$31,308	-	\$0
csc10.07-2	Tunnel, Portal and U-Wall (North King \ Bertania St \ S King St)	1	RF	\$25,129	-	\$0
csc10.07-3	Tunnel, Portal and U-Wall (Dillingham \ Bertania St \ S King St)	1	RF	\$25,129	-	\$0
csc10.07-4	Tunnel, Portal and U-Wall (King St Option 1 sta 1315+55 to 1408+91	1	RF	\$26,088	-	\$0
csc10.07-5	Tunnel, Portal and U-Wall (King St Option 2 sta 1348+50 to 1408+91	1	RF	\$27,920	-	\$0
10.07	Guideway: Underground tunnel		-			\$0
Guideway: Retained cut or fill						
csc10.08-1	Abutment Double At-Grade (Avg. D. T/R +10 Ft.) 100 ft length	1	RF	\$12,367	-	\$0
csc10.08-2	Abutment Single At-Grade (Avg. D. T/R +10 Ft.)	1	RF	\$6,162	-	\$0
10.08	Guideway: Retained cut or fill		RF			\$0
Track: Direct fixation						
csc10.09-1	Direct Fixation Track - Single	1	RF	\$435	-	\$0
csc10.09-2	Direct Fixation Dual Track	1	RF	\$675	14,524	\$9,803,700
10.09	Track: Direct fixation		RF			\$9,803,700
Track: Embedded/Paved						
csc10.10-1	Paved Track (In Street) - Single	1	RF	\$667	-	\$0
csc10.10-2	Paved Track (In Street) - DUAL	1	RF	\$1,250	-	\$0
10.10	Track: Embedded/Paved		RF			\$0
Track: Ballasted						
csc10.11-1	Ballasted Track (Open) - Single	1	RF	\$247	-	\$0
csc10.11-2	Ballasted Track (Open) - Double	1	RF	\$502	-	\$0
10.11	Track: Ballasted		RF			\$0
Track: Special (switches, turnouts)						
csc10.12-1	Double Crossover DF (No. 10)	1	EA	\$957,411	6	\$5,744,466
csc10.12-2	Double Crossover Ballasted (No. 10)	1	EA	\$804,040	-	\$0
csc10.12-3	No. 6 Turnout - DF	1	EA	\$282,314		\$0
csc10.12-4	No. 5 Turnout - DF	1	EA	\$135,258		\$0
csc10.12-5	Permanent Terminal, Direct Fixation	1	EA	\$24,549	2	\$49,098
csc10.12-6	Grade Crossing Panels (Dual Track)	1	EA	\$650	0	\$0
10.12	Track: Special (switches, turnouts)		LS			\$5,793,564
Track: Vibration and noise dampening						
csc10.13-1	Track Vibration and Noise Dampening	1	RF	\$1,074	\$ -	\$0
10.13	Vibration and noise dampening		RF			\$0
Total Guideways					\$134,413,774	

Honolulu High-Capacity Transit Corridor Project										Fixed Guideway Alternatives										Summary Cost Comparison of Alternative Analysis										Pricing Sheet										Station & Stops									
					SECTION 1					SECTION 2					SECTION 3					SECTION 4					SECTION 5																								
Saratoga Ave/North-South Rd from UHWO-Makai Station					Section 1 Alt 5					Fort Weaver Rd to Aloha Stadium					Salt Lake Blvd/Dillingham					Dillingham Blvd					St/Kapiolani Blvd to Ala Moana Sta					Section 1 Alt 5																			
					DESCRIPTION					COST					ID					QTY					UNIT																								
csc20.01-1					At-Grade Station - Split Side Platform (270 Ft. L.)					1					LS					\$3,195,536					RF					\$3,195,536																			
					20.01					AT GRADE STATIONS																																							
csc20.02-1					Aerial Station - SidePlatforms. Major (270 Ft. L.) Mezzanine					1					LS					\$5,940,590					RF					\$11,881,180																			
					2																																												
csc20.02-2					Aerial Station - SidePlatforms. Major (270 Ft. L.) No Mezzanine					1					LS					\$5,796,590					RF					\$11,881,180																			
					2																																												
csc20.02-3					Aerial Station - Stacked SidePlatforms. Major (270 Ft. L.) No Mezzanine					1					LS					\$6,140,810					RF					\$11,881,180																			
					2																																												
csc20.02-4					Aerial Station - Stacked SidePlatforms. Major (270 Ft. L.) Mezzanine					1					LS					\$6,284,810					RF					\$11,881,180																			
					2																																												
csc20.02-5					Aerial Station - Center Platforms. Major (270 Ft. L.) Mezzanine					1					LS					\$7,425,738					RF					\$11,881,180																			
					2																																												
csc20.03-1					Underground Station with Center Platform and Mezzanine					1					LS					\$85,172,231					RF					\$11,881,180																			
					2																																												
csc20.03-2					Underground Station with Center Platform without Mezzanine					1					LS					\$74,005,063					RF					\$11,881,180																			
					2																																												
20.03					UNDERGROUND STATIONS																				RF					\$0																			
					20.04					OTHER STATIONS & PEDESTRIAN TUNNELS					20.05					JOINT DEVELOPMENT															20.06					AUTOMOBILE PARKING MULTISTORY STRUCTURE									
csc20.07-1					ELEVATORS (40 ft Rise)					1					EA					\$454,508					RF					\$6,504,240																			
					4																																												
csc20.07-2					ELEVATORS (50 ft Rise)					1					EA					\$513,779					RF					\$6,504,240																			
					4																																												
csc20.07-3					ELEVATORS-RAPID RISE (70 ft Rise)					1					EA					\$645,336					RF					\$6,504,240																			
					4																																												
csc20.07-4					ESCALATORS (15 ft Rise)					1					EA					\$523,954					RF					\$6,504,240																			
					4																																												
csc20.07-5					ESCALATORS (30 ft Rise)					1					EA					\$585,776					RF					\$6,504,240																			
					4																																												
csc20.07-6					ESCALATORS (60 ft Rise)					1					EA					\$795,302					RF					\$6,504,240																			
					4																																												
Total STATIONS & STOPS																									RF					\$6,504,240																			

Honolulu High-Capacity Transit Corridor Project										Fixed Guideway Alternatives										Summary Cost Comparison of Alternative Analysis										Pricing Sheet										YARDS, SHOPS, ADMIN/SUPPORT FACILITIES																			
DESCRIPTION										COST										Systemwide																																							
1										2										3										4										5										UNIT									
30.00 YARDS, SHOPS, ADMIN/SUPPORT FACILITIES (20 ACRES)																																																											
ADMINISTRATION BUILDING: OFFICE, SALES, STORAGE, REVENUE COUNTING																																																											
Administration Building & Site Facilities																																																											
csc30.01-1																																																											
ADMINISTRATION BUILDING: OFFICE, SALES, STORAGE, REVENUE COUNTING																																																											
RF																																																											
30.01																																																											
HEAVY MAINTENANCE FACILITY																																																											
Storage Track & Running Repair Maintenance Bldg																																																											
Heavy Maintenance Facility and Yard																																																											
csc30.02-1																																																											
HEAVY MAINTENANCE FACILITY																																																											
LS																																																											
\$0																																																											
1																																																											
csc30.02-2																																																											
HEAVY MAINTENANCE FACILITY																																																											
Heavy Maintenance Facility and Yard																																																											
csc30.02-2																																																											
HEAVY MAINTENANCE FACILITY																																																											
LS																																																											
\$66,456,265																																																											
1																																																											
csc30.03																																																											
HEAVY MAINTENANCE FACILITY																																																											
RF																																																											
30.03																																																											
LIGHT MAINTENANCE FACILITY NOT USED*****																																																											
NOT USED																																																											
30.02																																																											
STORAGE BUILDING & YARD																																																											
NOT USED																																																											
30.04																																																											
MAINTENANCE OF WAY BUILDING & YARD NOT USED*****																																																											
NOT USED																																																											
30.05																																																											
MAINTENANCE OF WAY BUILDING & YARD NOT USED*****																																																											
NOT USED																																																											
30.06																																																											
MAINTENANCE OF WAY BUILDING & YARD NOT USED*****																																																											
NOT USED																																																											
30.07																																																											
MAINTENANCE OF WAY BUILDING & YARD NOT USED*****																																																											
NOT USED																																																											
30.08																																																											
MAINTENANCE OF WAY BUILDING & YARD NOT USED*****																																																											
NOT USED																																																											
30.09																																																											
MAINTENANCE OF WAY BUILDING & YARD NOT USED*****																																																											
NOT USED																																																											
30.10																																																											
MAINTENANCE OF WAY BUILDING & YARD NOT USED*****																																																											
NOT USED																																																											
30.11																																																											
MAINTENANCE OF WAY BUILDING & YARD NOT USED*****																																																											
NOT USED																																																											
30.12																																																											
STORAGE BUILDING & YARD																																																											
NOT USED																																																											
30.13																																																											
MAINTENANCE OF WAY BUILDING & YARD NOT USED*****																																																											
NOT USED																																																											
30.14																																																											
MAINTENANCE OF WAY BUILDING & YARD NOT USED*****																																																											
NOT USED																																																											
30.15																																																											
MAINTENANCE OF WAY BUILDING & YARD NOT USED*****																																																											
NOT USED																																																											
30.16																																																											
MAINTENANCE OF WAY BUILDING & YARD NOT USED*****																																																											
NOT USED																																																											
30.17																																																											
MAINTENANCE OF WAY BUILDING & YARD NOT USED*****																																																											
NOT USED																																																											
30.18																																																											
MAINTENANCE OF WAY BUILDING & YARD NOT USED*****																																																											
NOT USED																																																											
30.19																																																											
MAINTENANCE OF WAY BUILDING & YARD NOT USED*****																																																											
NOT USED																																																											
30.20																																																											
MAINTENANCE OF WAY BUILDING & YARD NOT USED*****																																																											
NOT USED																																																											
30.21																																																											
MAINTENANCE OF WAY BUILDING & YARD NOT USED*****																																																											
NOT USED																																																											
30.22																																																											
MAINTENANCE OF WAY BUILDING & YARD NOT USED*****																																																											
NOT USED																																																											
30.23																																																											
MAINTENANCE OF WAY BUILDING & YARD NOT USED*****																																																											
NOT USED																																																											
30.24																																																											
MAINTENANCE OF WAY BUILDING & YARD NOT USED*****																																																											
NOT USED																																																											
30.25																																																											
MAINTENANCE OF WAY BUILDING & YARD NOT USED*****																																																											
NOT USED																																																											
30.26																																																											
MAINTENANCE OF WAY BUILDING & YARD NOT USED*****																																																											
NOT USED																																																											
30.27																																																											
MAINTENANCE OF WAY BUILDING & YARD NOT USED*****																																																											
NOT USED																																																											
30.28																																																											
MAINTENANCE OF WAY BUILDING & YARD NOT USED*****																																																											
NOT USED																																																											
30.29																																																											
MAINTENANCE OF WAY BUILDING & YARD NOT USED*****																																																											
NOT USED																																																											
30.30																																																											
MAINTENANCE OF WAY BUILDING & YARD NOT USED*****																																																											
NOT USED																																																											
30.31																																																											
MAINTENANCE OF WAY BUILDING & YARD NOT USED*****																																																											
NOT USED																																																											
30.32																																																											
MAINTENANCE OF WAY BUILDING & YARD NOT USED*****																																																											
NOT USED																																																											
30.33																																																											
MAINTENANCE OF WAY BUILDING & YARD NOT USED*****																																																											
NOT USED																																																											
30.34																																																											
MAINTENANCE OF WAY BUILDING & YARD NOT USED*****																																																											
NOT USED																																																											
30.35																																																											
MAINTENANCE OF WAY BUILDING & YARD NOT USED*****																																																											
NOT USED																																																											
30.36																																																											
MAINTENANCE OF WAY BUILDING & YARD NOT USED*****																																																											
NOT USED																																																											
30.37																																																											
MAINTENANCE OF WAY BUILDING & YARD NOT USED*****																																																											
NOT USED																																																											
30.38																																																											
MAINTENANCE OF WAY BUILDING & YARD NOT USED*****																																																											
NOT USED																																																											
30.39																																																											
MAINTENANCE OF WAY BUILDING & YARD NOT USED*****																																																											
NOT USED																																																											
30.40																																																											
MAINTENANCE OF WAY BUILDING & YARD NOT USED*****																																																											
NOT USED																																																											
30.41																																																											
MAINTENANCE OF WAY BUILDING & YARD NOT USED*****																																																											
NOT USED																																																											
30.42																																																											
MAINTENANCE OF WAY BUILDING & YARD NOT USED*****																																																											
NOT USED																																																											
30.43																																																											
MAINTENANCE OF WAY BUILDING & YARD NOT USED*****																																																											
NOT USED																																																											
30.44																																																											
MAINTENANCE OF WAY BUILDING & YARD NOT USED*****																																																											
NOT USED																																																											
30.45																																																											
MAINTENANCE OF WAY BUILDING & YARD NOT USED*****																																																											
NOT USED																																																											
30.46																																																											
MAINTENANCE OF WAY BUILDING & YARD NOT USED*****																																																											
NOT USED																																																											
30.47																																																											
MAINTENANCE OF WAY BUILDING & YARD NOT USED*****																																																											
NOT USED																																																											
30.48																																																											
MAINTENANCE OF WAY BUILDING & YARD NOT USED*****																																																											
NOT USED																																																											
30.49																																																											
MAINTENANCE OF WAY BUILDING & YARD NOT USED*****																																																											
NOT USED																																																											
30.50																																																											
MAINTENANCE OF WAY BUILDING & YARD NOT USED*****																																																											
NOT USED																																																											
30.51																																																											
MAINTENANCE OF WAY BUILDING & YARD NOT USED*****																																																											
NOT USED																																																											
30.52																																																											
MAINTENANCE OF WAY BUILDING & YARD NOT USED*****																																																											
NOT USED																																																											
30.53																																																											
MAINTENANCE OF WAY BUILDING & YARD NOT USED*****																																																											
NOT USED																																																											
30.54																																																											
MAINTENANCE OF WAY BUILDING & YARD NOT USED*****																																																											
NOT USED																																																											
30.55																																																											
MAINTENANCE OF WAY BUILDING & YARD NOT USED*****																																																											
NOT USED																																																											
30.56																																																											
MAINTENANCE OF WAY BUILDING & YARD NOT USED*****																																																											
NOT USED																																																											
30.57																																																											
MAINTENANCE OF WAY BUILDING & YARD NOT USED*****																																																											
NOT USED																																																											
30.58																																																											
MAINTENANCE OF WAY BUILDING & YARD NOT USED*****																																																											
NOT USED																																																											
30.59																																																											
MAINTENANCE OF WAY BUILDING & YARD NOT USED*****																																																											
NOT USED																																																											

Honolulu High-Capacity Transit Corridor Project Fixed Guideway Alternatives Summary Cost Comparison of Alternative Analysis Pricing Sheet Sitework & Special Conditions									
						Saratoga Ave/North-South Rd from UHWO-Makai Station		Fort Weaver Rd to Aloha Stadium	
COST					UNIT				
ID	FTA Code	DESCRIPTION	QTY	UNIT	COST	Section 1 Alt 5		Section 2 Alt 1	
40.00 Sitework & Special Conditions			40.A 40.AG	AERIAL ALIGNMENT AT GRADE ALIGNMENT		12,363 6,906	33,274 2,300		
CSC40.01-1	Demolition: Urban		1	RF	\$207		\$0	35,574	\$7,363,818
CSC40.01-2	Demolition: Rural		1	RF	\$22		\$0		\$0
CSC40.01-3	Demolition: Residential		1	RF	\$53	6,906	\$366,018		\$0
CSC40.01-8	Clear and Grubbing		1	RF	\$62	34,000	\$2,108,000	1,600	\$99,200
CSC40.01-5	Earthwork		1	RF	in guideway				
CSC40.01-6	Building Mitigation (Underpinning, etc)		1	RF	\$4,672,938		\$0		\$0
CSC40.01-7	Building Mitigation (Parking Structure Demolition & Reconstruction)		1	SF	\$532		\$0		\$0
40.01 Demo Clearing & Sitework						\$2,474,018		\$35,574	\$7,463,018
CSC40.02-1	UTILITIES BASED ON 1992 INFORMATION		1	RF	\$81	19,269	\$1,560,789	35,574	\$2,881,494
CSC40.02-7	Utility: REMOVALS		1	RF	\$54	19,269	\$1,040,526	35,574	\$1,920,996
CSC40.02-8	SECTION 1: ELECTRICAL & COMMUNICATION- KAMOKILA BLVD		1	LS	\$11,661,300	-	\$0	-	\$0
CSC40.02-9	SECTION 1: ELECTRICAL & COMMUNICATION- KAPOLEI BLVD		1	LS	\$10,140,835	-	\$0	-	\$0
CSC40.02-10	SECTION 1: ELECTRICAL & COMMUNICATION- SARATOGA BLVD		1	LS	\$14,919,197	-	\$0	-	\$0
CSC40.02-10a	SECTION 1: ELECTRICAL & COMMUNICATION- MOS 1 SARATOGA BLVD		1	LS	\$9,914,625	1	\$9,914,625	-	\$0
CSC40.02-11	SECTION 1: ELECTRICAL & COMMUNICATION- GEIGER/FT WEAVER BLVD		1	LS	\$8,585,817	-	\$0	-	\$0
CSC40.02-12	SECTION 2: ELECTRICAL & COMMUNICATION- FARRINGTON BLVD		1	LS	\$12,628,933	-	\$0	1	\$12,628,933
CSC40.02-13	SECTION 3: ELECTRICAL & COMMUNICATION- SALT LAKE/NORTH KING BLVD		1	LS	\$16,069,810	-	\$0	-	\$0
CSC40.02-14	SECTION 3: ELECTRICAL & COMMUNICATION- SALT LAKE/DILLINGHAM BLVD		1	LS	\$15,489,716	-	\$0	-	\$0
CSC40.02-15	SECTION 3: ELECTRICAL & COMMUNICATION- MAUKA SIDE OF AIRPORT VIADUCT		1	LS	\$110,634,239	-	\$0	-	\$0
CSC40.02-16	SECTION 3: ELECTRICAL & COMMUNICATION- MAKAI SIDE OF AIRPORT VIADUCT ELEVATED		1	LS	\$90,946,739	-	\$0	-	\$0
CSC40.02-17	SECTION 3: ELECTRICAL & COMMUNICATION- MAUKA SIDE OF AIRPORT VIADUCT		1	LS	\$22,388,642	-	\$0	-	\$0
CSC40.02-18	SECTION 3: ELECTRICAL & COMMUNICATION- AOOLELE ST		1	LS	\$21,606,054	-	\$0	-	\$0
CSC40.02-19	SECTION 4: ELECTRICAL & COMMUNICATION- DILLINGHAM BLVD		1	LS	\$70,953,750	-	\$0	-	\$0
CSC40.02-20	SECTION 4: ELECTRICAL & COMMUNICATION- KING ST		1	LS	\$48,825,000	-	\$0	-	\$0
CSC40.02-21	SECTION 4: ELECTRICAL & COMMUNICATION- MIDDLE ST		1	LS	\$299,250	-	\$0	-	\$0
CSC40.02-22	SECTION 5: ELECTRICAL & COMMUNICATION- NORTH KING ST/HOTEL ST/KAWAIAHAO ST/KAPIOLANI BLVD		1	LS	\$133,610,175	-	\$0	-	\$0
CSC40.02-23	SECTION 5: ELECTRICAL & COMMUNICATION- DILLINGHAM BLVD/HOTEL ST/KAWAIAHAO ST/KAPIOLANI		1	LS	\$135,273,779	-	\$0	-	\$0
CSC40.02-24	SECTION 5: ELECTRICAL & COMMUNICATION- NORTH KING ST/WAIMANU ST/KAPIOLANI BLVD		1	LS	\$119,605,978	-	\$0	-	\$0
CSC40.02-24a	SECTION 5: ELECTRICAL & COMMUNICATION- MOS 1 NORTH KING ST/WAIMANU ST/KAPIOLANI BLVD		1	LS	\$9,497,964	-	\$0	-	\$0
CSC40.02-25	SECTION 5: ELECTRICAL & COMMUNICATION- DILLINGHAM BLVD/HOTEL ST/WAIMANU ST/KAPIOLANI		1	LS	\$121,269,582	-	\$0	-	\$0
CSC40.02-26	SECTION 5: ELECTRICAL & COMMUNICATION- NORTH KING ST/NIMITZ HWY/QUEEN ST/KAPIOLANI BLVD		1	LS	\$120,324,175	-	\$0	-	\$0
CSC40.02-62	SECTION 5: ELECTRICAL & COMMUNICATION- DILLINGHAM/NIMITZ/QUEENST/KAPIOLANI BLVD		1	LS	\$121,048,364	-	\$0	-	\$0
CSC40.02-63	SECTION 5: ELECTRICAL & COMMUNICATION- NORTH KING / NIMITZ / HALEKAUWILA ST / KAPIOLANI		1	LS	\$152,162,486	-	\$0	-	\$0
CSC40.02-63a	SECTION 5:MOS 2a :NORTH KING / NIMITZ / HALEKAUWILA ST / KAPIOLANI		1	LS	\$33,552,021	-	\$0	-	\$0
CSC40.02-63a1	SECTION 5:MOS 2a :DILLINGHAM / NIMITZ / HALEKAUWILA ST / KAPIOLANI		1	LS	\$34,290,694	-	\$0	-	\$0
CSC40.02-63b	SECTION 5: MOS 2b NORTH KING / NIMITZ / HALEKAUWILA ST / KAPIOLANI		1	LS	\$52,504,197	-	\$0	-	\$0
CSC40.02-63b1	SECTION 5: MOS 2b Dillingham / NIMITZ / HALEKAUWILA ST / KAPIOLANI		1	LS	\$53,242,870	-	\$0	-	\$0
CSC40.02-64	SECTION 5: ELECTRICAL & COMMUNICATION- DILLINGHAM / NIMITZ / HALEKAUWILA ST / KAPIOLANI		1	LS	\$152,983,234	-	\$0	-	\$0
CSC40.02-64a	SECTION 5: MOS 3 DILLINGHAM / NIMITZ / HALEKAUWILA ST / KAPIOLANI		1	LS	\$124,826,342	-	\$0	-	\$0
CSC40.02-65	SECTION 5: ELECTRICAL & COMMUNICATION- NORTH KING / BERETANIA ST / S KING ST		1	LS	\$61,198,973	-	\$0	-	\$0
CSC40.02-66	SECTION 5: ELECTRICAL & COMMUNICATION- DILLINGHAM / BERETANIA ST / S KING ST		1	LS	\$62,813,917	-	\$0	-	\$0
CSC40.02-68	SECTION 5: ELECTRICAL & COMMUNICATION- NORTH KING ST/WAIMANU ST/KAPIOLANI BLVD (short Tunnel King st)		1	LS	\$164,208,791	-	\$0	-	\$0
CSC40.02-69	SECTION 5: ELECTRICAL & COMMUNICATION- DILLINGHAM BLVD/HOTEL ST/WAIMANU ST/KAPIOLANI BLVD (long Tunnel King st		1	LS	\$165,872,395	-	\$0	-	\$0
CSC40.02-67	SECTION 5: ELECTRICAL & COMMUNICATION- WAIKIKI SPUR		1	LS	\$60,625,729	\$0 ok	\$0	\$0 ok	\$0
40.02 UTILITIES BASED ON 1992 INFORMATION			1	RF		\$12,515,940		\$17,431,423	
CSC40.03-1	Hazardous Material Mitigation: Petrochemical Contaminated Excavation		1	TON	\$185.00	1,283	\$237,355	17,571	\$3,250,635
CSC40.03-2	Hazardous Material Mitigation: Groundwater treatment		1	GAL	\$1	\$0	\$0	\$0	\$0
40.03 Hazardous Material Mitigation: Petrochemical Contaminated Excavation						\$237,355		\$3,250,635	
CSC40.04-1	Environmental Mitigation: Allowance for Biological and Archeological/Historical Monitoring		1	ALLOW		\$750,000		\$2,500,000	
40.04 Environmental mitigation, e.g. wetlands, historic/archeologic, parks						\$750,000		\$2,500,000	
Site Development: Roads, Walkways, Landscaping									
CSC40.06-1	Street Construction Adj. to LRT - One Lane		1	RF	\$295	0	\$0	33,974	\$10,022,330
CSC40.06-1a	Turn Pocket (100 ft)		1	RF	\$204	0	\$0	6,440	\$1,313,760
CSC40.06-17	Intersection Modification Type 1		1	LS	\$146,075	0	\$0	4	\$584,300
CSC40.06-18	Intersection Modification Type 2		1	LS	\$110,599	0	\$0	3	\$331,797
CSC40.06-19	Intersection Modification Type 3		1	LS	\$78,372	0	\$0	4	\$313,488
CSC40.06-21	Intersection Modification Type 4		1	LS	\$32,482	0	\$0	0	\$0
CSC40.06-10	Landscaping & Urban Design: Urban		1	RF	\$187		\$0		\$0
CSC40.06-11	Landscaping & Urban Design: Rural		1	RF	\$93		\$0		\$0
CSC40.06-12	Landscaping & Urban Design Based on 1992 Study		1	RF	\$130	19,269	\$2,504,970	35,574	\$4,624,620
CSC40.06-13	Hotel Street Mall Reconstruction		1	sf	\$160	0	\$0	0	\$0
CSC40.06-14	PARK & RIDE AT GRADE		1	STALL	\$4,543	2,800	\$12,720,400	0	\$0
CSC40.06-15	PARK & RIDE STRUCTURED		1	STALL	\$24,459	0	\$0	1,600	\$39,134,400
CSC40.06-15A	ACCESS RAMP TO P&R STRUCTURE		1	SQFT	\$440	40,000	\$17,600,000	92,377	\$40,645,880
CSC40.06-16	BUS BAYS		1	STALL	\$22,714	2	\$45,428	14	\$317,996
Public Art (2% of Section 20.00 Stations)						2% \$15,076,716	\$301,534	\$26,957,896	\$539,158
40.06 Site Development: Roads, Walkways, Landscaping						\$33,172,332		\$97,827,729	
Temporary Facilities									
40.08 Temporary Facilities									
Total Sitework & Special Conditions						49,149,645		128,472,805	

Honolulu High-Capacity Transit Corridor Project
Fixed Guideway Alternatives
Summary Cost Comparison of Alternative Analysis

Pricing Sheet
Sitework & Special Conditions

						Salt Lake Blvd/Dillingham Blvd		Dillingham Blvd	
COST ID	FTA Code	DESCRIPTION	QTY	UNIT	UNIT COST	Section 3 Alt 2		Section 4 Alt 3	
40.00 Sitework & Special Conditions			40.A 40.AG	AERIAL ALIGNMENT AT GRADE ALIGNMENT		24,972 0		8,793 0	
CSC40.01-1	Demolition: Urban		1	RF	\$207	24,972	\$5,169,204	8,793	\$1,820,151
CSC40.01-2	Demolition: Rural		1	RF	\$22		\$0		\$0
CSC40.01-3	Demolition: Residential		1	RF	\$53		\$0		\$0
CSC40.01-8	Clear and Grubbing		1	RF	\$62	0	\$0	0	\$0
CSC40.01-5	Earthwork		1	RF	in guideway				
CSC40.01-6	Building Mitigation (Underpinning, etc)		1	RF	\$4,672,938		\$0		\$0
CSC40.01-7	Building Mitigation (Parking Structure Demolition & Reconstruction)		1	SF	\$532		\$0		\$0
40.01 Demo Clearing & Sitework						\$5,169,204		\$1,820,151	
CSC40.02-1	UTILITIES BASED ON 1992 INFORMATION		1	RF	\$81	24,972	\$2,022,732	8,793	\$712,233
CSC40.02-7	Utility: REMOVALS		1	RF	\$54	24,972	\$1,348,488	8,793	\$474,822
CSC40.02-8	SECTION 1: ELECTRICAL & COMMUNICATION- KAMOKILA BLVD		1	LS	\$11,661,300	-	\$0	-	\$0
CSC40.02-9	SECTION 1: ELECTRICAL & COMMUNICATION- KAPOLEI BLVD		1	LS	\$10,140,835	-	\$0	-	\$0
CSC40.02-10	SECTION 1: ELECTRICAL & COMMUNICATION- SARATOGA BLVD		1	LS	\$14,919,197	-	\$0	-	\$0
CSC40.02-10a	SARATOGA BLVD		1	LS	\$9,914,625	-	\$0	-	\$0
CSC40.02-11	SECTION 1: ELECTRICAL & COMMUNICATION- GEIGER/FT WEAVER BLVD		1	LS	\$8,585,817	-	\$0	-	\$0
CSC40.02-12	SECTION 2: ELECTRICAL & COMMUNICATION- FARRINGTON BLVD		1	LS	\$12,628,933	-	\$0	-	\$0
CSC40.02-13	SECTION 3: ELECTRICAL & COMMUNICATION- SALT LAKE/NORTH KING BLVD		1	LS	\$16,069,810	-	\$0	-	\$0
CSC40.02-14	SECTION 3: ELECTRICAL & COMMUNICATION- SALT LAKE/DILLINGHAM BLVD		1	LS	\$15,489,716	1	\$15,489,716	-	\$0
CSC40.02-15	SECTION 3: ELECTRICAL & COMMUNICATION- MAUKA SIDE OF AIRPORT VIADUCT		1	LS	\$110,634,239	-	\$0	-	\$0
CSC40.02-16	SECTION 3: ELECTRICAL & COMMUNICATION- MAKAI SIDE OF AIRPORT VIADUCT ELEVATED		1	LS	\$90,946,739	-	\$0	-	\$0
CSC40.02-17	SECTION 3: ELECTRICAL & COMMUNICATION- MAUKA SIDE OF AIRPORT VIADUCT		1	LS	\$22,388,642	-	\$0	-	\$0
CSC40.02-18	SECTION 3: ELECTRICAL & COMMUNICATION- AOOLELE ST		1	LS	\$21,606,054	-	\$0	-	\$0
CSC40.02-19	SECTION 4: ELECTRICAL & COMMUNICATION- DILLINGHAM BLVD		1	LS	\$70,953,750	-	\$0	1	\$70,953,750
CSC40.02-20	SECTION 4: ELECTRICAL & COMMUNICATION- KING ST		1	LS	\$48,825,000	-	\$0	-	\$0
CSC40.02-21	SECTION 4: ELECTRICAL & COMMUNICATION- MIDDLE ST		1	LS	\$299,250	-	\$0	-	\$0
CSC40.02-22	SECTION 5: ELECTRICAL & COMMUNICATION- NORTH KING ST/HOTEL ST/KAWAIAHAO ST/KAPIOLANI BLVD		1	LS	\$133,610,175	-	\$0	-	\$0
CSC40.02-23	SECTION 5: ELECTRICAL & COMMUNICATION- DILLINGHAM BLVD/HOTEL ST/KAWAIAHAO ST/KAPIOLANI		1	LS	\$135,273,779	-	\$0	-	\$0
CSC40.02-24	SECTION 5: ELECTRICAL & COMMUNICATION- NORTH KING ST/WAIMANU ST/KAPIOLANI BLVD		1	LS	\$119,605,978	-	\$0	-	\$0
CSC40.02-24a	SECTION 5: ELECTRICAL & COMMUNICATION- MOS 1 NORTH KING ST/WAIMANU ST/KAPIOLANI BLVD		1	LS	\$9,497,964	-	\$0	-	\$0
CSC40.02-25	SECTION 5: ELECTRICAL & COMMUNICATION- DILLINGHAM BLVD/HOTEL ST/WAIMANU ST/KAPIOLANI		1	LS	\$121,269,582	-	\$0	-	\$0
CSC40.02-26	SECTION 5: ELECTRICAL & COMMUNICATION- NORTH KING ST/NIMITZ HWY/QUEEN ST/KAPIOLANI BLVD		1	LS	\$120,324,175	-	\$0	-	\$0
CSC40.02-62	SECTION 5: ELECTRICAL & COMMUNICATION- DILLINGHAM/NIMITZ/QUEENST/KAPIOLANI BLVD		1	LS	\$121,048,364	-	\$0	-	\$0
CSC40.02-63	SECTION 5: ELECTRICAL & COMMUNICATION- NORTH KING / NIMITZ / HALEKAUWILA ST / KAPIOLANI		1	LS	\$152,162,486	-	\$0	-	\$0
CSC40.02-63a	SECTION 5:MOS 2a :NORTH KING / NIMITZ / HALEKAUWILA ST / KAPIOLANI		1	LS	\$33,552,021	-	\$0	-	\$0
CSC40.02-63a1	SECTION 5:MOS 2a :DILLINGHAM / NIMITZ / HALEKAUWILA ST / KAPIOLANI		1	LS	\$34,290,694	-	\$0	-	\$0
CSC40.02-63b	SECTION 5: MOS 2b NORTH KING / NIMITZ / HALEKAUWILA ST / KAPIOLANI		1	LS	\$52,504,197	-	\$0	-	\$0
CSC40.02-63b1	SECTION 5: MOS 2b Dillingham / NIMITZ / HALEKAUWILA ST / KAPIOLANI		1	LS	\$53,242,870	-	\$0	-	\$0
CSC40.02-64	SECTION 5: ELECTRICAL & COMMUNICATION- DILLINGHAM / NIMITZ / HALEKAUWILA ST / KAPIOLANI		1	LS	\$152,983,234	-	\$0	-	\$0
CSC40.02-64a	SECTION 5: MOS 3 DILLINGHAM / NIMITZ / HALEKAUWILA ST / KAPIOLANI		1	LS	\$124,826,342	-	\$0	-	\$0
CSC40.02-65	SECTION 5: ELECTRICAL & COMMUNICATION- NORTH KING / BERETANIA ST / S KING ST		1	LS	\$61,198,973	-	\$0	-	\$0
CSC40.02-66	SECTION 5: ELECTRICAL & COMMUNICATION- DILLINGHAM / BERETANIA ST / S KING ST		1	LS	\$62,813,917	-	\$0	-	\$0
CSC40.02-68	SECTION 5: ELECTRICAL & COMMUNICATION- NORTH KING ST/WAIMANU ST/KAPIOLANI BLVD (short Tunnel King st)		1	LS	\$164,208,791	-	\$0	-	\$0
CSC40.02-69	SECTION 5: ELECTRICAL & COMMUNICATION- DILLINGHAM BLVD/HOTEL ST/WAIMANU ST/KAPIOLANI BLVD (long Tunnel King st		1	LS	\$165,872,395	-	\$0	-	\$0
CSC40.02-67	SECTION 5: ELECTRICAL & COMMUNICATION- WAIKIKI SPUR		1	LS	\$60,625,729	\$0 ok	\$0	\$0 ok	\$0
40.02 UTILITIES BASED ON 1992 INFORMATION			1	RF		\$18,860,936		\$72,140,805	
CSC40.03-1	Hazardous Material Mitigation: Petrochemical Contaminated Excavation		1	TON	\$185.00	834	\$154,290	12,504	\$2,313,240
CSC40.03-2	Hazardous Material Mitigation: Groundwater treatment		1	GAL	\$1	\$0	\$0	\$0	\$0
40.03 Hazardous Material Mitigation: Petrochemical Contaminated Excavation						\$154,290		\$2,313,240	
CSC40.04-1	Environmental Mitigation: Allowance for Biological and Archeological/Historical Monitoring		1	ALLOW		\$2,500,000		\$2,500,000	
40.04 Environmental mitigation, e.g. wetlands, historic/archeologic, parks						\$2,500,000		\$2,500,000	
Site Development: Roads, Walkways, Landscaping									
CSC40.06-1	Street Construction Adj. to LRT - One Lane		1	RF	\$295	18,500	\$5,457,500	9,702	\$2,862,090
CSC40.06-1a	Turn Pocket (100 ft)		1	RF	\$204	2,200	\$448,800	2,690	\$548,760
CSC40.06-17	Intersection Modification Type 1		1	LS	\$146,075	0	\$0	0	\$0
CSC40.06-18	Intersection Modification Type 2		1	LS	\$110,599	0	\$0	8	\$884,792
CSC40.06-19	Intersection Modification Type 3		1	LS	\$78,372	0	\$0	0	\$0
CSC40.06-21	Intersection Modification Type 4		1	LS	\$32,482	0	\$0	0	\$0
CSC40.06-10	Landscaping & Urban Design: Urban		1	RF	\$187		\$0		\$0
CSC40.06-11	Landscaping & Urban Design: Rural		1	RF	\$93		\$0		\$0
CSC40.06-12	Landscaping & Urban Design Based on 1992 Study		1	RF	\$130	24,972	\$3,246,360	8,793	\$1,143,090
CSC40.06-13	Hotel Street Mall Reconstruction		1	sf	\$160	0	\$0	0	\$0
CSC40.06-14	PARK & RIDE AT GRADE		1	STALL	\$4,543	1,650	\$7,495,950	0	\$0
CSC40.06-15	PARK & RIDE STRUCTURED		1	STALL	\$24,459	0	\$0	0	\$0
CSC40.06-15A	ACCESS RAMP TO P&R STRUCTURE		1	SOFT	\$440	0	\$0	0	\$0
CSC40.06-16	BUS BAYS		1	STALL	\$22,714	4	\$90,856	6	\$136,284
Public Art (2% of Section 20.00 Stations)						2%	\$11,737,180	\$234,744	\$17,821,770
40.06 Site Development: Roads, Walkways, Landscaping						\$16,974,210		\$5,931,451	
Temporary Facilities									
40.08 Temporary Facilities									
Total Sitework & Special Conditions						43,658,640		84,705,647	

Honolulu High-Capacity Transit Corridor Project
Fixed Guideway Alternatives
Summary Cost Comparison of Alternative Analysis

Pricing Sheet
Sitework & Special Conditions

						Dillingham/Nimitz Hwy/Halekauwila St/Kapiolani Blvd to Ala Moana Sta	
COST ID	FTA Code	DESCRIPTION	QTY	UNIT	UNIT COST	Section 1 Alt 5	
40.00 Sitework & Special Conditions			40.A 40.AG	AERIAL ALIGNMENT AT GRADE ALIGNMENT		14,524 0	
CSC40.01-1	Demolition: Urban		1	RF	\$207	14,524	\$3,006,468
CSC40.01-2	Demolition: Rural		1	RF	\$22		\$0
CSC40.01-3	Demolition: Residential		1	RF	\$53		\$0
CSC40.01-8	Clear and Grubbing		1	RF	\$62	0	\$0
CSC40.01-5	Earthwork		1	RF	in guideway		
CSC40.01-6	Building Mitigation (Underpinning, etc)		1	RF	\$4,672,938		\$0
CSC40.01-7	Building Mitigation (Parking Structure Demolition & Reconstruction)		1	SF	\$532		\$0
40.01 Demo Clearing & Sitework							\$3,006,468
CSC40.02-1	UTILITIES BASED ON 1992 INFORMATION		1	RF	\$81	14,524	\$1,176,444
CSC40.02-7	Utility: REMOVALS		1	RF	\$54	14,524	\$784,296
CSC40.02-8	SECTION 1: ELECTRICAL & COMMUNICATION- KAMOKILA BLVD		1	LS	\$11,661,300	-	\$0
CSC40.02-9	SECTION 1: ELECTRICAL & COMMUNICATION- KAPOLEI BLVD		1	LS	\$10,140,835	-	\$0
CSC40.02-10	SECTION 1: ELECTRICAL & COMMUNICATION- SARATOGA BLVD		1	LS	\$14,919,197	-	\$0
CSC40.02-10a	SARATOGA BLVD		1	LS	\$9,914,625	-	\$0
CSC40.02-11	SECTION 1: ELECTRICAL & COMMUNICATION- GEIGER/FT WEAVER BLVD		1	LS	\$8,585,817	-	\$0
CSC40.02-12	SECTION 2: ELECTRICAL & COMMUNICATION- FARRINGTON BLVD		1	LS	\$12,628,933	-	\$0
CSC40.02-13	SECTION 3: ELECTRICAL & COMMUNICATION- SALT LAKE/NORTH KING BLVD		1	LS	\$16,069,810	-	\$0
CSC40.02-14	SECTION 3: ELECTRICAL & COMMUNICATION- SALT LAKE/DILLINGHAM BLVD		1	LS	\$15,489,716	-	\$0
CSC40.02-15	SECTION 3: ELECTRICAL & COMMUNICATION- MAUKA SIDE OF AIRPORT VIADUCT		1	LS	\$110,634,239	-	\$0
CSC40.02-16	SECTION 3: ELECTRICAL & COMMUNICATION- MAKAI SIDE OF AIRPORT VIADUCT ELEVATED		1	LS	\$90,946,739	-	\$0
CSC40.02-17	SECTION 3: ELECTRICAL & COMMUNICATION- MAUKA SIDE OF AIRPORT VIADUCT		1	LS	\$22,388,642	-	\$0
CSC40.02-18	SECTION 3: ELECTRICAL & COMMUNICATION- AOOLELE ST		1	LS	\$21,606,054	-	\$0
CSC40.02-19	SECTION 4: ELECTRICAL & COMMUNICATION- DILLINGHAM BLVD		1	LS	\$70,953,750	-	\$0
CSC40.02-20	SECTION 4: ELECTRICAL & COMMUNICATION- KING ST		1	LS	\$48,825,000	-	\$0
CSC40.02-21	SECTION 4: ELECTRICAL & COMMUNICATION- MIDDLE ST		1	LS	\$299,250	-	\$0
CSC40.02-22	SECTION 5: ELECTRICAL & COMMUNICATION- NORTH KING ST/HOTEL ST/KAWAIAHAO ST/KAPIOLANI BLVD		1	LS	\$133,610,175	-	\$0
CSC40.02-23	DILLINGHAM BLVD/HOTEL ST/KAWAIAHAO ST/KAPIOLANI		1	LS	\$135,273,779	-	\$0
CSC40.02-24	SECTION 5: ELECTRICAL & COMMUNICATION- NORTH KING ST/WAIMANU ST/KAPIOLANI BLVD		1	LS	\$119,605,978	-	\$0
CSC40.02-24a	SECTION 5: ELECTRICAL & COMMUNICATION- MOS 1 NORTH KING ST/WAIMANU ST/KAPIOLANI BLVD		1	LS	\$9,497,964	-	\$0
CSC40.02-25	DILLINGHAM BLVD/HOTEL ST/WAIMANU ST/KAPIOLANI		1	LS	\$121,269,582	-	\$0
CSC40.02-26	SECTION 5: ELECTRICAL & COMMUNICATION- NORTH KING ST/NIMITZ HWY/QUEEN ST/KAPIOLANI BLVD		1	LS	\$120,324,175	-	\$0
CSC40.02-62	DILLINGHAM/NIMITZ/QUEENST/KAPIOLANI BLVD		1	LS	\$121,048,364	-	\$0
CSC40.02-63	SECTION 5: ELECTRICAL & COMMUNICATION- NORTH KING / NIMITZ / HALEKAUWILA ST / KAPIOLANI		1	LS	\$152,162,486	-	\$0
CSC40.02-63a	SECTION 5:MOS 2a :NORTH KING / NIMITZ / HALEKAUWILA ST / KAPIOLANI		1	LS	\$33,552,021	-	\$0
CSC40.02-63a1	SECTION 5:MOS 2a :DILLINGHAM / NIMITZ / HALEKAUWILA ST / KAPIOLANI		1	LS	\$34,290,694	-	\$0
CSC40.02-63b	SECTION 5: MOS 2b NORTH KING / NIMITZ / HALEKAUWILA ST / KAPIOLANI		1	LS	\$52,504,197	-	\$0
CSC40.02-63b1	SECTION 5: MOS 2b Dillingham / NIMITZ / HALEKAUWILA ST / KAPIOLANI		1	LS	\$53,242,870	-	\$0
CSC40.02-64	DILLINGHAM / NIMITZ / HALEKAUWILA ST / KAPIOLANI		1	LS	\$152,983,234	-	\$0
CSC40.02-64a	SECTION 5: MOS 3 DILLINGHAM / NIMITZ / HALEKAUWILA ST / KAPIOLANI		1	LS	\$124,826,342	1	\$124,826,342
CSC40.02-65	SECTION 5: ELECTRICAL & COMMUNICATION- NORTH KING / BERETANIA ST / S KING ST		1	LS	\$61,198,973	-	\$0
CSC40.02-66	SECTION 5: ELECTRICAL & COMMUNICATION- DILLINGHAM / BERETANIA ST / S KING ST		1	LS	\$62,813,917	-	\$0
CSC40.02-68	SECTION 5: ELECTRICAL & COMMUNICATION- NORTH KING ST/WAIMANU ST/KAPIOLANI BLVD (short Tunnel King st)		1	LS	\$164,208,791	-	\$0
CSC40.02-69	DILLINGHAM BLVD/HOTEL ST/WAIMANU ST/KAPIOLANI BLVD (long Tunnel King st		1	LS	\$165,872,395	-	\$0
CSC40.02-67	SECTION 5: ELECTRICAL & COMMUNICATION- WAIKIKI SPUR		1	LS	\$60,625,729	\$0 ok	\$0
40.02 UTILITIES BASED ON 1992 INFORMATION			1	RF			\$126,787,082
CSC40.03-1	Hazardous Material Mitigation: Petrochemical Contaminated Excavation		1	TON	\$185.00	-	\$0
CSC40.03-2	Hazardous Material Mitigation: Groundwater treatment		1	GAL	\$1	\$0	\$0
40.03 Hazardous Material Mitigation: Petrochemical Contaminated Excavation							\$0
CSC40.04-1	Environmental Mitigation: Allowance for Biological and Archeological/Historical Monitoring		1	ALLOW			\$750,000
40.04 Environmental mitigation, e.g. wetlands, historic/archeologic, parks							\$750,000
Site Development: Roads, Walkways, Landscaping							
CSC40.06-1	Street Construction Adj. to LRT - One Lane		1	RF	\$295	6,919	\$2,041,105
CSC40.06-1a	Turn Pocket (100 ft)		1	RF	\$204	3,100	\$632,400
CSC40.06-17	Intersection Modification Type 1		1	LS	\$146,075	0	\$0
CSC40.06-18	Intersection Modification Type 2		1	LS	\$110,599	0	\$0
CSC40.06-19	Intersection Modification Type 3		1	LS	\$78,372	1	\$78,372
CSC40.06-21	Intersection Modification Type 4		1	LS	\$32,482	1	\$32,482
CSC40.06-10	Landscaping & Urban Design: Urban		1	RF	\$187		\$0
CSC40.06-11	Landscaping & Urban Design: Rural		1	RF	\$93		\$0
CSC40.06-12	Landscaping & Urban Design Based on 1992 Study		1	RF	\$130	14,524	\$1,888,120
CSC40.06-13	Hotel Street Mall Reconstruction		1	sf	\$160	0	\$0
CSC40.06-14	PARK & RIDE AT GRADE		1	STALL	\$4,543	0	\$0
CSC40.06-15	PARK & RIDE STRUCTURED		1	STALL	\$24,459	0	\$0
CSC40.06-15A	ACCESS RAMP TO P&R STRUCTURE		1	SOFT	\$440	0	\$0
CSC40.06-16	BUS BAYS		1	STALL	\$22,714	-	\$0
Public Art (2% of Section 20.00 Stations)						2%	\$733,934
40.06 Site Development: Roads, Walkways, Landscaping							\$5,406,413
Temporary Facilities							
40.08 Temporary Facilities							
Total Sitework & Special Conditions			1	LS			135,949,963

Honolulu High-Capacity Transit Corridor Project Fixed Guideway Alternatives Summary Cost Comparison of Alternative Analysis Pricing Sheet Systems		
--	--	--

					Saratoga Ave/North-South Rd from UHWO-Makai Station		Fort Weaver Rd to Aloha Stadium	
		COST						
DESCRIPTION		ID	QTY	UNIT	Section 1 Alt 5		Section 2 Alt 1	
50.00 Systems				ALIGNMENT	30		9	
				19,269			35,574	
Train Control & Signals								
csc50.01-1	ATC, Signal System Line Stations	1	RF	\$238	19,269	\$4,586,022	\$35,574	\$8,466,612
csc50.01-2	Highway Crossing Warning Devices (Preemptive)	1	EA	\$235,278	8	\$1,882,224	\$0	\$0
50.01	Train Control & Signals		RF		\$6,468,246		\$8,466,612	
Guideway: At-grade semi-exclusive (allows cross-traffic) NOT USED*****					**NOT USED**		**NOT USED**	
Traffic Signals and Crossing Protection								
csc50.02-1	Traffic Signal Modifications (4 directions)	1	EA	\$376,047	0	\$0	\$13	\$4,888,611
csc50.02-2	Traffic Signal Modifications (3 directions)	1	EA	\$289,523	0	\$0	\$11	\$3,184,753
50.02	Traffic Signals and Crossing Protection		RF		\$0		\$8,073,364	
Traction Power Supply: Substations								
csc50.03-1	Traction Power Substations (2 MW)	1	EA	\$1,640,461	4	6,561,844	7	11,483,227
50.03	Traction Power Supply: Substations		RF		\$6,561,844		\$11,483,227	
Traction Power Distribution: Catenary and Third Rail								
csc50.04-1	Traction Power Supply - At-Grade OCS, Dual Track	1	RF	\$315	6,906	\$2,175,390	\$2,300	\$724,500
csc50.04-2	Traction Power Supply - Subway OCS, Double Track	1	RF	\$216	-	\$0	\$1,500	\$324,000
csc50.04-3	Traction Power Supply - Aerial OCS, Dual Track	1	RF	\$225	12,363	\$2,781,675	\$33,274	\$7,486,650
csc50.04-4	Traction Power Supply - Aerial OCS, Single Track	1	RF	\$170	-	\$0	\$0	\$0
50.04	Traction Power Distribution: Catenary and Third Rail		RF		\$4,957,065		\$8,535,150	
Communication								
csc50.05-1	Communications System - Dual Track	1	LS	\$299	19,269	\$5,761,431	\$35,574	\$10,636,626
50.05	Communication		-		\$5,761,431		\$10,636,626	
Fare Collection System and Equipment								
csc50.06-1	Fare Vending Equipment Underground Stations	1	LS	\$584,612	-	\$0	-	\$0
csc50.06-2	Fare Vending Equipment Aerial & At Grade Stations	1	LS	\$299,712	3	\$899,136	5	\$1,498,560
50.06	Fare Collection System and Equipment		RF		\$899,136		\$1,498,560	
Central Control								
csc50.07	Central Control Facility	1	LS	\$8,529,933	-	\$0	-	\$0
50.07	Central Control		RF		\$0		\$0	
Total Systems					\$24,647,722		\$48,693,539	

Honolulu High-Capacity Transit Corridor Project Fixed Guideway Alternatives Summary Cost Comparison of Alternative Analysis Pricing Sheet Systems								
					Salt Lake Blvd/Dillingham Blvd		Dillingham Blvd	
DESCRIPTION					section 3		section 4	
COST					11		18	
ID QTY UNIT								
50.00 Systems					ALIGNMENT			
					24,972		8,793	
Train Control & Signals								
csc50.01-1	ATC, Signal System Line Stations	1	RF	\$238	\$24,972	\$5,943,336	\$8,793	\$2,092,734
csc50.01-2	Highway Crossing Warning Devices (Preemptive)	1	EA	\$235,278	\$0	\$0	\$0	\$0
50.01	Train Control & Signals		RF		\$5,943,336		\$2,092,734	
Guideway: At-grade semi-exclusive (allows cross-traffic) NOT USED*****					**NOT USED**		**NOT USED**	
Traffic Signals and Crossing Protection								
csc50.02-1	Traffic Signal Modifications (4 directions)	1	EA	\$376,047	\$6	\$2,256,282	\$6	\$2,256,282
csc50.02-2	Traffic Signal Modifications (3 directions)	1	EA	\$289,523	\$10	\$2,895,230	\$2	\$579,046
50.02	Traffic Signals and Crossing Protection		RF		\$5,151,512		\$2,835,328	
Traction Power Supply: Substations								
csc50.03-1	Traction Power Substations (2 MW)	1	EA	\$1,640,461	5	8,202,305	2	3,280,922
50.03	Traction Power Supply: Substations		RF		\$8,202,305		\$3,280,922	
Traction Power Distribution: Catenary and Third Rail								
csc50.04-1	Traction Power Supply - At-Grade OCS, Dual Track	1	RF	\$315	\$0	\$0	\$0	\$0
csc50.04-2	Traction Power Supply - Subway OCS, Double Track	1	RF	\$216	\$0	\$0	\$0	\$0
csc50.04-3	Traction Power Supply - Aerial OCS, Dual Track	1	RF	\$225	\$24,972	\$5,618,700	\$8,793	\$1,978,425
csc50.04-4	Traction Power Supply - Aerial OCS, Single Track	1	RF	\$170	\$0	\$0	\$0	\$0
50.04	Traction Power Distribution: Catenary and Third Rail		RF		\$5,618,700		\$1,978,425	
Communication								
csc50.05-1	Communications System - Dual Track	1	LS	\$299	\$24,972	\$7,466,628	\$8,793	\$2,629,107
50.05	Communication		-		\$7,466,628		\$2,629,107	
Fare Collection System and Equipment								
csc50.06-1	Fare Vending Equipment Underground Stations	1	LS	\$584,612	-	\$0	-	\$0
csc50.06-2	Fare Vending Equipment Aerial & At Grade Stations	1	LS	\$299,712	2	\$599,424	3	\$899,136
50.06	Fare Collection System and Equipment		RF		\$599,424		\$899,136	
Central Control								
csc50.07	Central Control Facility	1	LS	\$8,529,933	-	\$0	-	\$0
50.07	Central Control		RF		\$0		\$0	
Total Systems					\$32,981,905		\$13,715,652	

Honolulu High-Capacity Transit Corridor Project Fixed Guideway Alternatives Summary Cost Comparison of Alternative Analysis Pricing Sheet Systems	
--	--

						Dillingham/Nimitz Hwy/Halekauwila St/Kapiolani Blvd to Ala Moana Sta			
			COST					Systemwide	
DESCRIPTION			ID	QTY	UNIT	Section 1 Alt 5		Section 6	
50.00 Systems					ALIGNMENT	14,524	37	0	38
Train Control & Signals									
csc50.01-1	ATC, Signal System Line Stations			1	RF	\$238	\$14,524	\$3,456,712	\$0
csc50.01-2	Highway Crossing Warning Devices (Preemptive)			1	EA	\$235,278	\$0	\$0	\$0
50.01	Train Control & Signals				RF		\$3,456,712		\$0
Guideway: At-grade semi-exclusive (allows cross-traffic) NOT USED*****						**NOT USED**		**NOT USED**	
Traffic Signals and Crossing Protection									
csc50.02-1	Traffic Signal Modifications (4 directions)			1	EA	\$376,047	\$13	\$4,888,611	\$0
csc50.02-2	Traffic Signal Modifications (3 directions)			1	EA	\$289,523	\$5	\$1,447,615	\$0
50.02	Traffic Signals and Crossing Protection				RF		\$6,336,226		\$0
Traction Power Supply: Substations									
csc50.03-1	Traction Power Substations (2 MW)			1	EA	\$1,640,461	3	4,921,383	\$0
50.03	Traction Power Supply: Substations				RF		\$4,921,383		\$0
Traction Power Distribution: Catenary and Third Rail									
csc50.04-1	Traction Power Supply - At-Grade OCS, Dual Track			1	RF	\$315	\$0	\$0	\$0
csc50.04-2	Traction Power Supply - Subway OCS, Double Track			1	RF	\$216	\$0	\$0	\$0
csc50.04-3	Traction Power Supply - Aerial OCS, Dual Track			1	RF	\$225	\$14,524	\$3,267,900	\$0
csc50.04-4	Traction Power Supply - Aerial OCS, Single Track			1	RF	\$170	\$0	\$0	\$0
50.04	Traction Power Distribution: Catenary and Third Rail				RF		\$3,267,900		\$0
Communication									
csc50.05-1	Communications System - Dual Track			1	LS	\$299	\$14,524	\$4,342,676	\$0
50.05	Communication				-		\$4,342,676		\$0
Fare Collection System and Equipment									
csc50.06-1	Fare Vending Equipment Underground Stations			1	LS	\$584,612	-	\$0	\$0
csc50.06-2	Fare Vending Equipment Aerial & At Grade Stations			1	LS	\$299,712	6	\$1,798,272	\$0
50.06	Fare Collection System and Equipment				RF		\$1,798,272		\$0
Central Control									
csc50.07	Central Control Facility			1	LS	\$8,529,933	-	\$0	\$8,529,933
50.07	Central Control				RF		\$0		\$8,529,933
Total Systems							\$24,123,169	\$8,529,933	

Honolulu High-Capacity Transit Corridor Project Fixed Guideway Alternatives Summary Cost Comparison of Alternative Analysis						
Pricing Sheet Vehicles Summary Cost Comparison of Alternative Analysis						
Vehicles Cost Summary						
COST ID	DESCRIPTION	20-mile Alignment QTY	UNIT	UNIT COST	20-mile Alignment COST	
70.00 Vehicles						
CSC70.01	Articulated LRV	66	EA	\$2,466,732	\$162,804,312	
70.01	TOTAL		EA		\$162,804,312	
CSC70.06	Non Revenue Vehicles	1	LS	\$4,203,149	\$4,203,149	
70.06	TOTAL		LS		\$4,203,149	
CSC70.07	Spare Parts	66	EA	\$246,673	\$16,280,418	
70.07	TOTAL		EA		\$16,280,418	
Total Vehicles					\$183,287,879	