For inclusion in HHCTCP Chapter 4.18.5…

During final design, DTS, in cooperation with its contractors and FTA, will develop a Construction Mitigation Plan (CMP). Per requirements of FTA Noise and Vibration Impact assessment (2006) guidance, DTA shall perform quantitative assessments of both noise and vibration which will inform the CMP. Noise and vibration control plans will be updated every six months. The updated plans should predict the construction noise and vibration impacts at sensitive receptor locations based upon the proposed construction equipment and methods. Appropriate construction plan noise and vibration mitigation measures shall be employed. These measures are identified in FTA's guidance manual (2006).